


SET eXPerience
Pilot Project for Next Generation Terrestrial
TV Broadcasting in Brazil

NEC Corporation



1. Outline of the project

Pilot Project on Next-generation Digital Terrestrial Broadcasting Technology in Brazil



Period : Up to Mar. 2021











Place : Rio de Janeiro, Brazil

Objectives :

- Introducing test environment of advanced digital terrestrial broadcasting technologies developed in Japan.
- The advanced DTT platform for trial test will be established in Rio de Janeiro in Brazil.



2. Project Implementation Schedule

- ✓ NEC support the establishment of the advanced ISDB-T transmission equipment and its testing in Rio de Janeiro.
- ✓ Transmission test of this trial equipment is expected to be started at the beginning of next year.

		2020				2021		
Description	Month	Sep	Oct	Nov	Dec	Jan	Feb	Mar
Event					SET eXPerience			
1. Preparation of trial equipment in Japan								
2. Testing at factory in Japan								
3. Delivery & custom clearance of trial equipment								
4. Installations of the test environment in Brazil								
5. Introduction of Project in SET Exhibition								
6. Operation and testing by the SBTVDF.								
7. Joint evaluation with NEC (Expected to be done remotely)								
8. Wrap-up Meeting								

3.0 Condition of Factory Test in Japan

- ✓ NEC prepared the following equipment and tested 4K program transmission with advanced ISDB-T transmission equipment.
- ✓ NEC confirmed 4K program reception and transmission parameter of the advanced ISDB-T system.



3.1 Explanation of Equipment

4K Player and 4K Monitor

- 4K Player : 3G-SDI x 4 output
- GPS Receiver : 10MHz, Black Burst and NTP Output
- GOP Generator : Group of Picture reference output
- 4K Monitor : 12G input
- Audio Monitor : 12G input and 32ch audio indication

4K Player



GPS Receiver

GOP Generator

4K Monitor



Audio Monitor

3.1 Explanation of Equipment

4K Encoder

- 4K and 2K H.265 MMT Encoder module
- Video I/O : 4K (2,160p) and 2K (1,080p/i)
- Audio I/O : Embedded Audio, 32ch
- Video Encoding : H.265|HEVC Main10 Profile
- Audio Encoding : MPEG-4 AAC (ISO/IEC 14496-3)
- 4K I/O : 3G-SDI x 4 and 12G-SDI

4K Decoder

- 4K H.265 TLV/MMT Decoder
- IP Input : MMT/IP Input
- 4K Output : 3G-SDI x 4 or 12G-SDI signal



YE-9300
Encoder



MF4400
Mounting Shelf



4K XJive MMT Decoder

3.2 Explanation of Equipment

Re-Multiplexer

- IP Input : MMT/TLV input of layer-A, B, C and LLch-1 system
- IP Output : Two XMI packets to the Modulator
- Multiplexing: FCE Block process, Frame process and XMI packet

Modulator

- IP Input : XMI/IP input
- IF Output : H1, H2, V1 and V2
- Output frequency : 37.15MHz and 10dBm \pm 1dB/50ohm
- Modulation : Bit-Interleaved Coded Mod and Hierarchical Synthesis
- Interleave : Time and Frequency Interleave



Re-multiplexer

Modulator


3.3 Explanation of Equipment

Exciter and TX Controller

- IF Input : OFDM modulation signal (37.15MHz)
- RF Output : OFDM modulation wave
- Bandwidth : 5.57MHz and 35 segments (H polarization)

Demodulator

- IF Input : H1, H2, V1 and V2
- IP Output : MMT/IP
- Output frequency : 37.15MHz and 10dBm±1dB/50ohm
- Modulation : Bit-Interleaved Coded Mod and Hierarchical Synthesis
- Interleave : Time and Frequency Interleave




4.1 Transmission Parameter of factory test

Transmission Parameter of Factory Test

The following transmission parameters in each equipment is set and 4K program reception is confirmed.


- Modulation : Non-Uniform Constellation (NUC), **256QAM**
- Error correction : LDPC (12/16) + BCH
- FFT : 16k
- GI ratio : $800/16384 \doteq 1/21$ (126 μ s)
- Band width : 5.83MHz at Exciter output
- Variable pilot insertion ratio
- System : **SISO**



4.2 Transmission Parameter of factory test

NEC also conducted Factory Test in accordance with following parameters.

- Video coding : 2K/4K, 20Mbps to 30Mbps
- Modulation : QPSK, 16QAM, 64QAM, 256QAM, 1024QAM, 4096QAM
- Error correction : LDPC(2/16 to 14/16) + BCH
- FFT : 8K, 16K, 32K
- GI ratio : 126.56us to 648us



4.3 Transmission Parameter of factory test

NEC will prepare following measuring instrument for measurement of next generation system in Brazil.

(1)Advanced signal analyzer

- Constellation, Frequency Response, Delay Profile, TMCC
- Input Level, MER


(2)TLV Packet Analyzer

- BER (PN)
- PER (TLV packet)

(3) Spectrum Analyzer

- Wideband spectrum measurement such as Adjacent channels

Advanced
Signal
Analyzer




TLV Packet Analyzer




5.1 Block Diagram of Factory Test


Transmission System



Receiving System




Sync System




5.2 Block Diagram in Brazil


Transmission System




Receiving System



Sync System



Existing TX Rack



6.1 Transmission Test Plan in Rio de Janeiro

- ✓ Encoder and Re-multiplexer will be installed in Studio Station.
- ✓ Transmission line between Studio and TX station will be used existing IP route.
- ✓ Modulator and Exciter will be installed in existing TX Rack in TX Station.

Map of Transmission Route in Rio de Janeiro



6.2 Transmission Test Plan in Rio de Janeiro

Measurement of Advance ISDB-T Transmission System


- ✓ Field Transmission Test in Rio de Janeiro will be conducted.
- ✓ Following items are expected to be measured by field analyzer.
- ✓ Characteristic against ISDB-Tb reception will be compared.

Characteristics of Signal Transmission

- Signal Reception Level
- MER (Modulation Error Ratio)
- BER (Bits Error Rate)
- Chanel Spectrum
- Constellation
- Delay Profile

Quality Check of Video and Audio

- Bit Rate of Video Cording
- Bit Rate of Audio Cording
- Error Collection and Interleave
- Guard Interval and Delay Profile
- Carrier Modulation



 **Orchestrating** a brighter world

NEC